

BRUHAT BANGALORE MAHANAGARA PALIKE
"SCHEDULE - B"

Name of Work: Improvements to CC Road from Shakil House, Makthum sab House and Hazere House Roads at MS Palya in Ward No. 11 (Kuvempunagara), Vidyaranyapura Sub Division.


Tender Number : BBMP/2012-13/RD/WORK_INDENT4596

SNo	Item Name	Unit	Estimate Quantity	Approved Rates	
				In Figure	In Words
1	Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	117.7	100.00	Rupees One Hundred Only
2	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, coarse aggregates @ 0.85 cum and fine aggregates @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	122.7	3800.00	Rupees Three Thousand Eight Hundred Only
3	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	78.9	150.00	Rupees One Hundred Fifty Only
4	Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing & technical etc complete as per specifications and directions of engineer in charge of the work	M	84	150.00	Rupees One Hundred Fifty Only




Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

SNo	Item Name	Unit	Estimate Quantity	Approved Rates	
				In Figure	In Words
5	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregates @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	81.8	4937.76	Rupees Four Thousand Nine Hundred Thirty Seven And Paise Seventy Six Only
6	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratory, Power Floater, blade and disc etc complete as per specifications and directions of engineer in charge of the work	Sqm	818	156.50	Rupees One Hundred Fifty Six And Paise Fifty Only
7	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	117.7	120.00	Rupees One Hundred Twenty Only


Contractor


Executive Engineer
Byatarayanapura Division
Bruhat Bangalore Mahanagara Palike